



icmr
INDIAN COUNCIL
OF
MEDICAL
RESEARCH

NIN
NATIONAL INSTITUTE
OF NUTRITION

आई सी एम आर - राष्ट्रीय पोषण संस्थान
स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य और परिवार
कल्याण मंत्रालय, भारत सरकार

ICMR – National Institute of Nutrition
Department of Health Research, Ministry of Health
and Family Welfare, Government of India

No.NIN/Maint/Q18/2021-22/98

Date: 08.11.2021

TENDER NOTICE

The Director, ICMR-National Institute of Nutrition, Tarnaka, Hyderabad invites sealed tenders by **23.11.2021** at 5.00 PM from reputed, experienced contractors/agencies with established experience and financial solvency to carry out the **“Replace the Asbestos sheet with GI sheet to the table tennis and carrom room”**. The details of the work are as follows:


S. No	Description	Unit	Qty	Rate	Amount in Rs.
1.	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement: 6 coarse sand).	Cum	10.00		
2.	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement: 3 coarse sand) finished rough with sponge.	Sqm	45.00		
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: 13.43.1 Water thinnable cement primer	Sqm	45.00		
4	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	Sqm	45.00		
5.	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade: Old work (one or more coats)	Sqm	325.00		
6.	Demolishing brick work manually/ by mechanical means including stacking of	Cum	10.00		

	serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar				
7	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos cement sheet	Sqm	56.90		
8	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	Sqm	150.00		

Terms and conditions

1. The sealed cover should be super- scribed **“Replace the Asbestos sheet with GI sheet to the table tennis and carrom room”** with last date.
2. Water & Electricity will be provided by ICMR-NIN, Hyderabad to the contractor.
3. The quotation should be addressed to “The Director, ICMR-National Institute of Nutrition, Hyderabad”.
4. The offer/quotation in sealed cover should reach the undersigned by **5.00 PM** on or before **23.11.2021** and hand over in the Dispatch Section/ Maintenance Department. The offer/quotation received thereafter will not be considered. ICMR-NIN, Hyderabad is not responsible for any postal delays.
5. It is the responsibility of the contractor to visit the site before submitting their offer/quotation, for which the bidder may contact I/c Maintenance at 040-27197226/312 on all working days i.e. Monday to Friday except public holidays from 09.00 AM to 05.30 PM.

6. Quotation should submit in contractor letter head and sign in each page.
7. Certificate of Registration for **Goods and Services Tax (GST)**.
8. **Percentage of tax (GST) and amount** should be mentioned separately in the quotation.
9. Discount offered, if any, may be indicated as a percentage of the order value only.
10. The work shall be completed within 30 days from the date of award of the work
11. The TDS will be recovered as per rules
12. The labour engaged and working equipment brought by the contractor for the work shall be recorded in the ICMR-NIN Security Gate before entering into the premises and obtain necessary gate pass.
13. Payment will be made against the bill along with a statement of measurement taken in the presence of the contractor and the civil engineer of ICMR-NIN, Hyderabad.
14. The contractor/bidder should indicate their Registration Number, PAN, GST, Bank Account number for making payments to the contractor as well as statutory authorities.
15. Quotation by email or fax will not be accepted.
16. The ICMR-NIN, Hyderabad is not responsible for any damage caused to the labour/manpower engaged by the contractor for execution of the work.
17. Bills submitted by the contractor will be settled after certification by the Civil Engineer of NIN with regard to its quality. Any defect in the work has to be rectified free of cost by the contractor within six months from the date of completion of the work.
18. ICMR-NIN, Hyderabad is not responsible for payment of wages to the manpower engaged by the contractor and statutory dues for the work at ICMR-NIN.
19. Director, ICMR-NIN, Hyderabad has the right to accept or reject any quotation(s) without assigning any reasons
20. Director, ICMR-NIN, Hyderabad reserves the right to increase/decrease the quantity of work.



Co-Convenor (Maintenance & Security)
For Director