



icmr | **NIN**

INDIAN COUNCIL OF
MEDICAL RESEARCH

NATIONAL INSTITUTE
OF NUTRITION

आईसीएमआर - राष्ट्रीय पोषण संस्थान
स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य और परिवार
कल्याण मंत्रालय, भारत सरकार

ICMR - National Institute of Nutrition,
DHR, Ministry of Health & Family Welfare,
Government of India.

Ref No: ICMR-NIN/EMS/2024-25/180823/012

Date: 30/4/2024

Notice Inviting Tender(s)

The Director, ICMR-National Institute of Nutrition, Tarnaka, Hyderabad invites sealed tenders by 15-05-2024 at 17.00 Hrs. from reputed, experienced contractors/agencies with established experience and financial solvency to carry out the Renovation of Liquid Nitrogen Room, ICMR-NIN, Hyderabad. The details of the work are as follows: -

Sl. No.	Description	Unit	Qty	Rate (INR)	Amount (INR)
1	Removal of window	LS	1		
2	3 Track UPVC sliding window of size 1.2m *1.2m	LS	1		
2	Dismantling precast concrete or stone slabs in walls, partition walls etc. including stacking within 50 meters lead:				
3	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero-chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, levelling system and rubber mallet for placing the tiles gently and easily.				
	Glazed vitrified floor tiles polished finish of size 11.41A.2.1 Size of Tile 600 x 600 mm	Sqm	15		
4	8 mm thick granite stone tiles (mirror polished of all shades)	Sqm	15		
5	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mmthick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or				

	even bigger size dash fastener if require, fixed with Galvanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic raw plugs at 450mm centre to centre and 40 mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in- Charge.				
	With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles	Sqm	15		
		GST (If any)			
		Total			

Terms & Conditions

1. The sealed cover should be superscribed "Renovation of Liquid Nitrogen Room, ICMR-NIN, Hyderabad, ICMR-NIN, Hyderabad" with last date.
2. Water & Electricity will be provided by ICMR-NIN, Hyderabad to the contractor.
3. The quotation should be addressed to "The Director, ICMR-National Institute of Nutrition, Hyderabad".
4. The offer/quotation in sealed cover should reach the undersigned by 17:00 Hrs. on or before 15-05-2024 and hand over in the Dispatch Section/ Maintenance Department. The offer/quotation received thereafter will not be considered. ICMR-NIN, Hyderabad is not responsible for any postal delays.
5. It is the responsibility of the contractor to visit the site before submitting their offer/quotation, for which the bidder may contact I/c Maintenance at 040-27197226/312 on all working days i.e., Monday to Friday except public holidays from 09:00 Hrs. to 17:30 Hrs.
6. Quotation should submit in contractor letter head with signature in each page.
7. Certificate of Registration for Goods and Services Tax (GST).
8. Percentage of tax (GST) and amount should be mentioned separately in the quotation.
9. Discount offered, if any, may be indicated as a percentage of the order value only.
10. The work shall be completed within 30 days from the date of award of the work.
11. The TDS will be recovered as per rules.
12. The labour engaged and working equipment brought by the contractor for the work shall be recorded in the ICMR-NIN Security Gate before entering into the premises and obtain necessary gate pass.
13. Payment will be made against the bill along with a statement of measurement taken in the presence of the contractor and the Civil Engineer of ICMR-NIN, Hyderabad.
14. The contractor/bidder should indicate their Registration Number, PAN, GST, Bank Account number for making payments to the contractor as well as statutory authorities.
15. Quotation by email or fax will not be accepted.
16. The ICMR-NIN, Hyderabad is not responsible for any damage caused to the labour/manpower engaged by the contractor for execution of the work.
17. Bills submitted by the contractor will be settled after certification by the Civil Engineer of NIN with regard to its quality. Any defect in the work has to be rectified free of cost by the contractor within six months from the date of completion of the work.
18. ICMR-NIN, Hyderabad is not responsible for payment of wages to the manpower engaged by the contractor and statutory dues for the work at ICMR-NIN.
19. Director, ICMR-NIN, Hyderabad has the right to accept or reject any quotation(s) without assigning any reasons.
20. Director, ICMR-NIN, Hyderabad reserves the right to increase/decrease the quantity of work.

Yours sincerely,


 (B Venkateshwar Rao)
 Technical Officer C
 For Director

To: -

1. Convener - to upload the same in NIN's website NIN Website Management Committee.
2. The Director, Centre for Cellular and Molecular Biology, Uppal Road, Habsiguda, Hyderabad, Telangana 500007.
3. The Director, Indian Institute of Chemical Technology, Uppal Road, IICT Colony, Tarnaka, Hyderabad, Telangana 500007.
4. The Director, National Geophysical Research Institute, Uppal Road, Habsiguda, Hyderabad, Telangana 500007.
5. The Chief Administrative Officer, Nuclear Fuel Complex, ECIL, Moula-Ali, Hyderabad, Telangana 500062.
6. The Chief Administrative Officer, Rail Nilayam, SD Road, East Marredpally, Secunderabad, Telangana 500071.
7. The Executive Engineer, Central Public Works Department, Sultan Bazar, Koti, Hyderabad-500095.