



**icmr**  
INDIAN COUNCIL  
OF  
MEDICAL  
RESEARCH

**NIN**

NATIONAL INSTITUTE  
OF NUTRITION

आई सी एम आर - राष्ट्रीय पोषण संस्थान  
स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य और परिवार  
कल्याण मंत्रालय, भारत सरकार

ICMR – National Institute of Nutrition  
Department of Health Research, Ministry of Health  
and Family Welfare, Government of India

No.NIN/Maint/Q3/2020/05

Date: 15.05.2020

**TENDER NOTICE**

The Director, ICMR-National Institute of Nutrition, Tarnaka, Hyderabad invites sealed tenders till **27.05.2020** at 03.00 PM from reputed, experienced contractors/agencies with established experience and financial solvency to carry out the **Proposed Welfare Clinic at Old Sub-station Building**. The details of the work are as follows:-

S.No	Description	Unit	Qty	Rate	Amount
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m including pointing the joints with white cement and matching pigments etc., complete. 5.80 x 7.0 = 40.60	Sq.m	41.00		
2	Brick work 7 cm thick with common burnt clay F.P.S. (non modular) brick of class designation 7.5 in cement mortar 1:3 (1 cement : 3 coarse sand) in superstructure above plinth level and upto floor five level.	Sq.m	10.00		
3	20 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	Sq.m	18.00		
4	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels	Sq.m	41.00		

	<p>45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :</p> <ul style="list-style-type: none"> <li>➤ 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095-(Part I) : 2011 (Board with BIS certification marks)</li> <li>➤ 5.80 x 7.0= 40.60</li> </ul>				
5.	<p>Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.</p>	Sq.m	12.00		

6.	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer. $2 \times (5.80 + 7.00) \times 3.35 = 85.76 \text{ Sq.m}$	Sq.m	104.00		
7	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete ➤ White solid plastic seat with lid	No	01		
8	4" PVC pipe	Rmt	10		
	<b>Total</b>				

### Terms and conditions

1. The sealed cover should be super- scribed "Proposed Welfare Clinic at Old Sub-station Building."
2. Water will be provided by NIN, Hyderabad to the contractor.
3. The quotation should be addressed to "The Director, National Institute of Nutrition, Hyderabad".
4. The offer/quotation in sealed cover should reach the undersigned by **3.00 PM on or before 27.05.2020** along with **EMD 5% of the estimate cost** as Demand draft/Bank cheque/ Pay order of schedule bank and drawn in favour of **Director NIN, Hyderabad**) in Quotation Drop box at Maintenance Department. The offer/quotation received thereafter will not be considered. NIN, Hyderabad is not responsible for any postal delays. The sealed tenders will be opened on **27.05.2020 at 3.30 PM** in the office of Civil Engineer, NIN, Hyderabad.
5. It is the responsibility of the contractor to visit the site before submitting their offer/quotation, for which the bidder may contact Technical Officer (C) at 040-27197226/312 on all working days i.e. Monday to Friday except public holidays from 09.00 AM to 05.30 PM.
6. Director, NIN, Hyderabad has the right to accept or reject any quotation(s) without assigning any reasons.
7. The work shall be completed within 30 days from the date of award of the work.
8. The labour engaged and working equipment brought by the contractor for the work shall be recorded in the NIN Security Gate before entering into the premises and obtain necessary gate pass.
9. Payment will be made against the bill along with a statement of measurement taken in the presence of the contractor and the civil engineer of NIN, Hyderabad.

10. The contractor/bidder should indicate their Registration Number, PAN, GST, Bank Account number for making payments to the contractor as well as statutory authorities.
11. Quotation by email or fax will not be accepted.
12. The NIN, Hyderabad is not responsible for any damage caused to the labour/manpower engaged by the contractor for execution of the work.
13. Bills submitted by the contractor will be settled after certification by the Civil Engineer of NIN with regard to its quality. Any defect in the work has to be rectified free of cost by the contractor within six months from the date of completion of the work.
14. NIN, Hyderabad is not responsible for payment of wages to the manpower engaged by the contractor and statutory dues for the work at NIN.
15. Director, NIN, Hyderabad reserves the right to increase/decrease the quantity of work.

*M. Krishna*  
15/05/2020

*[Signature]*  
Technical Officer -C  
Maintenance Department  
For Director

To

1. Convener, - to upload the same in NIN's website NIN Website Management Committee
2. The Director, Centre for Cellular and Molecular Biology Uppal Road, Habsiguda, Hyderabad, Telangana 500007
3. The Director, Indian Institute of Chemical Technology, Uppal Road, IICT Colony, Tarnaka, Hyderabad, Telangana 500007
4. The Director, National Geophysical Research Institute, Uppal Road, Habsiguda, Hyderabad, Telangana 500007
5. The Chief Administrative Officer, Nuclear Fuel Complex, ECIL, Moula-ali, Hyderabad, Telangana 500062.
6. The Chief Administrative Officer, Rail Nilayam, SD Road, East Marredpally, Secunderabad, Telangana 500071.