



**icmr**  
INDIAN COUNCIL OF  
MEDICAL RESEARCH

**NIN**  
NATIONAL INSTITUTE  
OF NUTRITION

आईसीएमआर - राष्ट्रीय पोषण संस्थान  
स्वास्थ्य अनुसंधान विभाग, स्वास्थ्य और परिवार  
कल्याण मंत्रालय, भारत सरकार  
ICMR - National Institute of Nutrition,  
DHR, Ministry of Health & Family Welfare,  
Government of India.

Ref No: ICMR-NIN/EMS/2025-26/235539/148

Date: 21-05-2025

**Notice Inviting Tender(s)**

The Director, ICMR-National Institute of Nutrition, Tarnaka, Hyderabad invites sealed tenders by **11-06-2025** at **17.00 Hrs.** from reputed, experienced contractors/agencies with established experience and financial solvency to carry out the work - **"Replacement of Drainage Line behind B-Type Quarters, ICMR-NIN, Hyderabad"**. The details of the work are as follows: -

Sl. No.	Description	Unit	Qty	Rate (INR)	Amount (INR)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. ----- All kinds of soil.	m <sup>3</sup>	7.00		
2	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56 m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design : ----- 0.91 m deep with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, foot rests and 12 mm thick cement plaster at the external surface shall be paid for separately) : ----- With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	3.00		
3	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain	Each	2.00		

तारनाका, जमाई उस्मानिया पोस्ट, हैदराबाद - ५००००७, भारत  
Tarnaka, Jamai-Osmania PO, Hyderabad - 500007, India.

Tel: +914027197226  
www.nin.res.in

	etc. complete : ----- For pipes 100 to 250 mm diameter				
4	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : ----- 150 mm diameter	m	20.00		
5	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design : ----- 150 mm diameter S.W. pipe	m	20.00		
6	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150 mm dia upto 300 mm	m	20.00		
				GST (If any)	
				Total	

#### Terms & Conditions

1. The sealed cover should be superscribed "**Replacement of Drainage Line behind B-Type Quarters, ICMR-NIN, Hyderabad.**" with last date.
2. Water & Electricity will be provided by ICMR-NIN, Hyderabad to the contractor.
3. The quotation should be addressed to "**The Director, ICMR-National Institute of Nutrition, Hyderabad**".
4. The offer/quotation in sealed cover should reach the undersigned by **17:00 Hrs.** on or before **11-06-2025** along with **EMD Rs.5000/-** as Demand Draft/Bankers Cheque/Pay Order of Scheduled Banks drawn in favour of **THE DIRECTOR NIN** payable at Hyderabad and hand over in the Dispatch Section/ Maintenance Department. The offer/quotation received thereafter will not be considered. ICMR-NIN, Hyderabad is not responsible for any postal delays.
5. It is the responsibility of the contractor to visit the site before submitting their offer/quotation, for which the bidder may contact I/c Maintenance at 040-27197226/312 on all working days i.e., Monday to Friday except public holidays from 09:00 Hrs. to 17:30 Hrs.
6. Quotation should be submitted in contractor's letter head with signature in each page.
7. Certificate of Registration for Goods and Services Tax (GST).
8. Percentage of tax (GST) and amount should be mentioned separately in the quotation.
9. Discount offered, if any, may be indicated as a percentage of the order value only.
10. The work shall be completed within 30 days from the date of award of the work.
11. The TDS will be recovered as per rules.
12. The labour engaged and working equipment brought by the contractor for the work shall be recorded in the ICMR-NIN Security Gate before entering into the premises and obtain necessary gate pass.
13. Payment will be made against the bill along with a statement of measurement taken in the presence of the contractor and the Civil Engineer of ICMR-NIN, Hyderabad.
14. The contractor/bidder should indicate their Registration Number, PAN, GST, Bank Account number for making payments to the contractor as well as statutory authorities.
15. Quotation by email or fax will not be accepted.

16. The ICMR-NIN, Hyderabad is not responsible for any damage caused to the labour/manpower engaged by the contractor for execution of the work.
17. Bills submitted by the contractor will be settled after certification by the Civil Engineer of NIN with regard to its quality. Any defect in the work has to be rectified free of cost by the contractor within six months from the date of completion of the work.
18. ICMR-NIN, Hyderabad is not responsible for payment of wages to the manpower engaged by the contractor and statutory dues for the work at ICMR-NIN.
19. Director, ICMR-NIN, Hyderabad has the right to accept or reject any quotation(s) without assigning any reasons.
20. Director, ICMR-NIN, Hyderabad reserves the right to increase/decrease the quantity of work.

  
(B Venkateshwar Rao)  
Technical Officer C  
For Director

To: -

1. Convener - to upload the same in NIN's website NIN Website Management Committee.
2. The Director, Centre for Cellular and Molecular Biology, Uppal Road, Habsiguda, Hyderabad, Telangana 500007.
3. The Director, Indian Institute of Chemical Technology, Uppal Road, IICT Colony, Tarnaka, Hyderabad, Telangana 500007.
4. The Director, National Geophysical Research Institute, Uppal Road, Habsiguda, Hyderabad, Telangana 500007.
5. The Chief Administrative Officer, Nuclear Fuel Complex, ECIL, Moula-Ali, Hyderabad, Telangana 500062.
6. The Execute Engineer, Central Public Works Department, Sultan Bazar, Koti, Hyderabad-500095.